



01	EXISTING DEMISING / MASCONRY WALL TO REMAIN
02	INSTALL NEW NON-RATED PARTITION AS INDICATED
03	NEW TIEOUT RM. - INSTALL NEW RIGID INSULATED GLASS UNIT (IGU) ACCESSIBLE TIEOUT ROOM (87" TURNING CIRCLE) INCLUDING TIEOUT TO RYAN BOWL GRAB BARS PER BC 1109.1, ICCA 117.1 CHAPTER 6
04	INSTALL WATERPROOF CERAMIC FLOOR TILES & 6" HIGH CERAMIC BASE AS REQUIRED (TYPICAL)
05	INSTALL NEW 36" ADA ACCESSIBLE TIEOUT
06	COMMERCIAL UNIT ENTRY DOOR ACCESSIBLE, 1 HOUR FIRE PROVE SELF-CLOSING METAL DOOR (MIN. 36" WITH 10" CLEARANCE) ABOUT TO REMAIN
07	INSTALL NEW PENTRY CABINET WITH SINK & DISHWASHER CONNECTED TO RELOCATED PLUMBING RISER
08	EXISTING WINDOWS TO REMAIN, REPAIR IF REQUIRED
09	EXISTING GLAZED ACCESS DOOR TO REMAIN
10	INSTALL NEW NON-RATED PLUMBING WALLS AS INDICATED
12	EXISTING FIRE ESCAPE TO REMAIN
13	REPAIR OR INSTALL NEW WOOD FLOOR AND REPAIR OR INSTALL NEW GWC ON ALL EXISTING WALLS AS REQUIRED
14	INSTALL NEW METAL PWSB ENTRANCE DOOR WITH DEAD BOLT AND MORTISED ENTRY LOCK
15	INSTALL NEW METAL PWSB DOOR WITH MORTISED ENTRY LOCK
16	INSTALL NEW OR RELOCATE EXISTING ELECTRICAL CIRCUIT PANEL