



FURNITURE, POWER & COMMUNICATIONS NOTES	
1.	ALL ELECTRICAL AND TELEPHONE OUTLETS SHALL BE MOUNTED AT HEIGHT 15" ABOVE FINISH FLOOR (A.F.F.), VERTICALLY, U.O.N.
2.	ALL CABLE INSTALLED IN CEILING AND UNDER FLOOR TO BE TEFLON COATED.
3.	ALL ELECTRICAL AND TELEPHONE SERVICE TO BE RECESSED INSTALLATION U.O.N.
4.	ALL SEPARATE CIRCUITS AND DEDICATED ELECTRICAL OUTLETS TO HAVE COLOR CODED DEVICES.
5.	M.A.D.G.I. DRAWINGS SHALL BE USED FOR DIMENSIONED LOCATIONS AND HEIGHT OF ALL ELECTRICAL FIXTURES AND RECEPTACLES.
6.	ALL TELEPHONE AND COMMUNICATION CABLEING TO BE SUPPLIED AND INSTALLED BY THE TENANT CONTRACTOR.
7.	ENGINEER TO VERIFY AMPERAGE AND OUTLET REQUIREMENTS FOR ALL SEPARATE CIRCUITS AND DEDICATED OUTLETS.
8.	ALL ELECTRICAL PANELS WILL BE COORDINATED BETWEEN THE ENGINEER AND M.A.D.G.I. FOR SUITABLE LOCATIONS.
9.	ALL NEW LIGHT SWITCH AND RECEPTACLE COVER PLATES TO BE COLOR WHITE U.O.N.
10.	ALL ELECTRICAL AND TELEPHONE WORK TO BE PER ALL APPLICABLE CODES, LOCAL LAWS & AGENCIES.
11.	ALL FURNITURE AND EQUIPMENT SUPPLIED BY TENANT.
12.	ALL OPENINGS FOR OUTLETS (COMMUNICATION, ELECTRICAL, & FURNITURE WHIPS) AT HOLLOW FIRE-RATED CONSTRUCTION SHALL BE SLEEVED WITH SHEET METAL AT LEAST NO. 14 U.S. STANDARD GAUGE THICK AS PER N.Y.C. BUILDING CODE 27-343.
13.	CONTRACTOR TO COORDINATE WITH FURNITURE VENDOR FOR ALL FINAL WIRING AT ALL FURNITURE WORKSTATIONS AS REQUIRED.
14.	CONTRACTOR TO PROVIDE THE FOLLOWING CIRCUITING (TYP.): <div>A. ALL DEDICATED DUPLEX OUTLETS TO BE QUANTITY (1) PER CIRCUIT</div> <div>B. ALL CONVENIENCE OUTLETS TO BE QUANTITY (6) PER CIRCUIT</div>
15.	ALL OUTLETS TO BE RECESSED UNLESS OTHERWISE NOTED. FURR OUT WALLS WHERE NECESSARY. PERIMETER AND CORE WALLS CANNOT BE CHOPPED.

FURNITURE, POWER & COMMUNICATIONS LEGEND					
▶	NEW RECESSED WALL MOUNTED TELEPHONE OUTLET	GFI@	NEW RECESSED WALL MOUNTED DUPLEX ELECTRICAL OUTLET W/GROUND FAULT INTERRUPTER	DB	DOOR BELL
▷	NEW RECESSED WALL MOUNTED DATA OUTLET	#	NEW RECESSED WALL MOUNTED QUAD ELECTRICAL OUTLET	DR	DOOR RELEASE BUTTON
▶	NEW RECESSED WALL MOUNTED TELEPHONE/DATA OUTLET	⊖	NEW EQUIPMENT SPECIFIED CIRCUIT SEE ENGINEERING DRAWINGS FOR DETAIL	IR	DOOR INFRARED RELEASE
▣	NEW FLOOR MOUNTED TELEPHONE/DATA OUTLET	----	CONTINUOUS PLUG MOLD STRIP	ES	ELECTRIC STRIKE
▣	NEW FURNITURE MOUNTED TELEPHONE/DATA OUTLET	=====	TRENCHING FOR ELEC/TELECOM WIRING	EC	ELECTRIC CLOCK
⊖	NEW RECESSED WALL MOUNTED DUPLEX ELECTRICAL OUTLET	P/T	NEW FLOOR MOUNTED POWER FEED FOR WORKSTATIONS	ML	MAGNETIC LOCK
▣	NEW FLOOR MOUNTED DUPLEX ELECTRICAL OUTLET	P/T	NEW WALL/COLUMN MOUNTED POWER FEED FOR WORKSTATIONS	PB	PANIC BUTTON
⊙	NEW CEILING MOUNTED DUPLEX ELECTRICAL OUTLET	TV	NEW CABLE TV CONNECTION, WALL-MOUNTED		
▣	NEW FURNITURE MOUNTED DUPLEX ELECTRICAL OUTLET	I	INTERCOM		
⊖	NEW RECESSED WALL MOUNTED DUPLEX ELECTRICAL OUTLET W/DEDICATED CIRCUIT 20A 120V	CR	CARD READER		
					HATCH PATTERN DENOTES 'MILLWORK'
					HATCH PATTERN DENOTES 'NOT IN SCOPE'

KEY PLAN:
5TH AVENUE
54TH STREET
N

CONSULTANTS:
NOT FOR CONSTRUCTION
ISSUED FOR REVIEW

BULLETIN 1: ISSUED FOR CONSTRUCTION	12/29/14
ISSUED FOR LL REVIEW	12/19/14
ISSUED FOR BID AND LL REVIEW	10/29/14
ISSUED FOR: SCOPE OF WORK	10/21/14
ISSUE NAME	DATE

PROJECT NAME:
MCM
681 5TH AVE
NEW YORK, NY 10022
7TH FLR CONST. / 10TH FLR RENTAL

SHEET NAME:
FURNITURE, POWER & COMMUNICATIONS PLAN

SEAL & SIGNATURE:
MONTROND DEMARCO, LLP

DATE: 10/16/14
PROJECT NO.: 14106
PRINCIPAL: SA
DRAWING BY: SK
CHECKED BY: AW
SCALE: 1/8"=1'-0"
DWG No.:
A-400.00
9 of 12