

GENERAL POWER & DATA NOTES

1. GENERAL: CONTRACTOR SHALL VERIFY THE AVAILABLE ELECTRIC SERVICE IN THE TENANT'S SPACE AND ADVISE THE ARCHITECT OF ANY DISCREPANCIES PRIOR TO SUBMITTING A S.D.
2. ELECTRICAL CONTRACTOR SHALL DISCONNECT, CONNECT AND PROVIDE NECESSARY ELECTRIC RACE IN ORDER TO CONFORM WITH THE TENANT'S SPACE AND ADVISE THE ARCHITECT OF ANY DISCREPANCIES PRIOR TO SUBMITTING A S.D.
3. SWITCHES, DUPLEX OUTLETS, COVER PLATES AND FLOOR MOUNTED OUTLETS SHALL BE INSTALLED BY CONTRACTOR NEARBY IN A FIRST CLASS FINISH.
4. IF APPLICABLE, THE CONTRACTOR SHALL INSTALL NEW YORK CITY APPROVED OUTLETS ONLY.
5. IF OUTLET DIMENSION CALLS FOR MORE THAN 24" AFF., OUTLETS WITHIN EQUIPMENT OF WALL, TELEPHONE OUTLETS, SHALL BE MOUNTED/LOCATED TO CENTERLINE DIMENSIONS OF ANY OUTLET PAIR SHALL NOT EXCEED 12".
6. ALL BACK TO BACK OUTLETS ADJOINING ROOMS TO BE STAGGERED.
7. ALL EXISTING TO REMAIN ELECTRICAL OUTLETS SHALL BE REWIRED WITH NEW RECEPTABLES AND FLOOR MOUNTED OUTLETS.
8. ALL NEW TELEPHONE AND ELECTRICAL OUTLETS TO BE INSTALLED ON AN EXISTING WALL, SHOULD BE FLUSH MOUNTED WITH THE FINISHED WALL SURFACE. CHOP OUT THE WALL AS REQUIRED TO RECESS THE JUNCTION BOX AND CONDUIT AND PATCH THE WALL AS REQUIRED.
9. ALL EXISTING ELECTRICAL OUTLETS TO BE CARRIED SHALL HAVE THE ELECTRICAL SERVICE AND ALL THE WIRING REMOVED, RECEPTABLE AS REQUIRED.
10. GENERAL: CONTRACTOR SHALL REMOVE ALL UNUSED CONDUIT, CABLE AND TELEPHONE WIRING COMPLETELY FROM AREAS IN SCOPE OF THIS CONTRACT.
11. GENERAL: CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK NECESSARY TO COMPLETE CORP. FINISHES AND ELECTRICAL HOOKUP, PATCHING, ETC. INCLUDING WORK IN LANDSCAPE OR OUTSIDE OF TENANT'S SPACE. ALL CODE, ORDINANCE, SHALL BE ACCOMPLISHED DURING STATED BUILDING APPROVED WORKING HOURS. CONTRACTOR SHALL VERIFY AND CONFORM TO THOSE RULES, ORDINANCES AND REQUIREMENTS.
12. SHOULD JOB CONDITIONS REQUIRE RELOCATION OF PLANNED TELEPHONE OR ELECTRICAL OUTLETS FOR ANY REASON, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT FIELD REPRESENTATIVE FOR APPROVAL OF ALTERNATE LOCATION PRIOR TO THE START OF ANY WORK.
13. ALL EXISTING WALL OUTLETS WHICH DO NOT INTERFERE WITH NEW CONSTRUCTION SHALL REMAIN.
14. ALL EXISTING FIRE ALARM DEVICES OR WALL BONES WHICH INTERFERE WITH NEW PARTITION WORK SHALL BE RELOCATED TO AN APPROVED LOCATION.
15. GENERAL: CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND HOOK UP OF ALL ELECTRIFIED DEVICES THROUGH THE EXISTING ELECTRICAL SYSTEM AS SPECIFIED BY THE ARCHITECT. CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE HIMSELF WITH THE EXISTING ELECTRICAL SYSTEMS AND ALL ELECTRICAL WORK RELATED TO THIS SYSTEM.
16. DO NOT INSTALL TELEPHONE AND ELECTRICAL RECEPTABLE FLOOR OUTLETS INTO SAME FLOOR AREAS.
17. NO FLOOR OR WALL POWER OUTLETS SHALL BE CONNECTED TO LIGHTING CIRCUITS.
18. GENERAL: CONTRACTOR SHALL REUSE AND UPDATE LABELS FOR ALL CIRCUIT BREAKERS AT ALL ELECTRICAL CLOSETS ON THE JOB.
19. TELEPHONE CLOSET AND WALL OUTLET RACKS SHALL BE CARRIED OF WALL FOLLOWING THE TELEPHONE COMPANY'S PREWRITTEN STANDARD CONNECTIONS, BOTH FOR SINGLELINE EXTENSIONS AND FOR CALL DIRECTORIES.
20. WHERE SPECIFIED, CONDUIT OR SUB-CONDUITS SHALL BE RUN IN CONDUIT OR IN CASE OF COLLISION, A NOTCH SHALL BE CUT IN WALL USING AN CORNER RUNNING PARALLEL TO WALLS, COLLARING BEAMS AND OTHER CONDUITS TO AVOID CONTACT POINT OF HORIZONTAL CONDUIT AT EACH POINT. CONDUIT TO RUN HORIZONTALLY TO ACTUAL LOCATION OF OUTLET AS DIMENSIONED ON PLAN.
21. G.C. SHALL COORDINATE WITH THE ELECTRICAL & WOODWORK CONTRACTORS TO PROVIDE OUTLET IN FIELD AS REQUIRED FOR EXTENSION OF ELECTRICAL OUTLETS, CABLES, ETC. INTO CABINETS/STOVE AS SPECIFIED.
22. THE ELECTRICAL CONTRACTOR SHALL INCLUDE AND COORDINATE FAN, WATER HEATERS AND SPECIAL EQUIPMENT, EXHAUST FANS, ETC. WITH THE BUILDING AND MECHANICAL CONTRACTOR'S REQUIREMENTS AND REQUIREMENTS INCLUDING THE INSTALLATION OF REQUIRED CONDUIT FROM THE BUILDING TELEPHONE EQUIPMENT ROOM TO THE TENANT'S SPACE.
23. GENERAL: CONTRACTOR TO PROVIDE (1) AIRPROOF FIRE RETARDING BARRIER UNLESS IN WOOD PANEL OR IN FINISH AS INDICATED ON THE PLAN FOR THE TELEPHONE EQUIPMENT INSTALLATION, UNLESS OTHERWISE NOTED.

EQUIPMENT SYMBOLS

- INDICATES CLIENT SUPPLIED COPPER
- INDICATES CLIENT SUPPLIED TELEVISION
- INDICATES CLIENT SUPPLIED MICROWAVE
- INDICATES CLIENT SUPPLIED REFRIGERATOR
- INDICATES CLIENT SUPPLIED COMPACT REFRIG.
- INDICATES CLIENT SUPPLIED COFFEE MAKER
- INDICATES CLIENT SUPPLIED WATERCOOLER

SECURITY DOOR SYSTEM

- WALL MOUNTED CARD READER FOR CLIENTS SECURITY CARD KEY SYSTEM WITH 8" CONDUIT WITHIN PARTITION TO 8" ABOVE FINISHED CEILING WITH ORANGE USE TO THE ARCHITECT TO VERIFY AFF. OF 8" AFF. UNLESS OTHERWISE NOTED.
- WALL MOUNTED DOOR RELEASE BUTTON MOUNTED AT 3" AFF. UNLESS OTHERWISE NOTED. REFER TO SECURITY CONTRACTOR FOR ADDITIONAL INFORMATION. PROVIDE CONDUIT WITHIN PARTITION TO 8" ABOVE FINISHED CEILING.
- WALL MOUNTED DOOR RELEASE BUTTON MOUNTED AT 3" AFF. UNLESS OTHERWISE NOTED.
- WALL MOUNTED DOOR BELL WITH 8" CONDUIT TO 8" ABOVE FINISHED CEILING, MOUNTED AT 3" AFF.
- MAGNETIC (MAG) LOCK SET
- PASSIVE INFRA RED MOTION SENSOR DOOR RELEASE MECHANISM MOUNTED IN CEILING.

ELECTRICAL LEGEND


- WALL MOUNTED DUPLEX ELECTRICAL OUTLET / RECEPTACLE MOUNTED AT 18" AFF., UNLESS OTHERWISE NOTED.
- WALL MOUNTED DUPLEX ELECTRICAL OUTLET / RECEPTACLE MOUNTED AT 18" AFF., UNLESS OTHERWISE NOTED.
- WALL MOUNTED DOOR RELEASE BUTTON MOUNTED AT 3" AFF. UNLESS OTHERWISE NOTED.
- WALL MOUNTED SEPARATE CIRCUIT DUPLEX ELECTRICAL OUTLET / RECEPTACLE MOUNTED AT 18" AFF., UNLESS OTHERWISE NOTED.
- WALL MOUNTED SEPARATE CIRCUIT QUADRUPLE ELECTRICAL OUTLET / RECEPTACLE MOUNTED AT 18" AFF., UNLESS OTHERWISE NOTED.
- FURNITURE MOUNTED POWER AND DATA OUTLET SUPPLIED BY FURNITURE VENDOR
- *SHIP LOCATION FOR NEW ELECTRICAL FEED VIDEO DATA WIRING

- GENERAL NOTES:
1. ALL WORK SHALL CONFORM TO ALL STATE AND LOCAL BUILDING CODES AND REGULATIONS.
 2. FINAL LAYOUT TO BE APPROVED BY ARCHITECT (AND DESIGNER PRIOR TO FRAMING).
 3. G.C. SHALL PROVIDE ALL BLOCKING FOR WALL MTS. CABINETS, SHELVE, ETC.
 4. ALL DOORS SHALL BE UNDERCUT TO ACCOMMODATE NEW OR EXISTING FINISHED FLOOR.
 5. ALL EXISTING CONSTRUCTION SHALL BE PATCHED OR LAMINATED TO ACCEPT PAINT.
 6. CONTRACTOR SHALL ARRANGE WITH BLDG. MANAGER FOR ALL DELIVERIES AND ELEVATOR NEEDS.

GENERAL NOTE:

1. ALL WORK SHALL CONFORM TO ALL STATE AND LOCAL BUILDING CODES AND REGULATIONS.
2. FINAL LAYOUT TO BE APPROVED BY ARCHITECT (AND DESIGNER PRIOR TO FRAMING).
3. G.C. SHALL PROVIDE ALL BLOCKING FOR WALL MTS. CABINETS, SHELVE, ETC.
4. ALL DOORS SHALL BE UNDERCUT TO ACCOMMODATE NEW OR EXISTING FINISHED FLOOR.
5. ALL EXISTING CONSTRUCTION SHALL BE PATCHED OR LAMINATED TO ACCEPT PAINT.
6. CONTRACTOR SHALL ARRANGE WITH BLDG. MANAGER FOR ALL DELIVERIES AND ELEVATOR NEEDS.

KEYED PLAN



REVISION	DATE	DESCRIPTION
NO.	DATE	DESCRIPTION
1	AUG. 18, 2009	REVIEW ONLY, PRELIMINARY
2	AUG. 20, 2009	ISSUED FOR BLDG. REVIEW

SCALE: AS NOTED

PROJECT: 483 7TH AVE., NEW YORK, NY 10018

DRAWING: 6TH FLOOR PLAN, BUREAU 601 POWER AND DATA PLAN

